

12" wide Cast-in-Place Trench Drain vs. Zurn Z882-DGC

	Cast-in-Place (CIP)	Plug-in-Cost	Z-882	Plug-in-Cost
<i>No. of Channel Sections</i>	None		13	
<i>Frame & Grate Sections</i>	50 pieces Pre-assembled at Factory		13 - 8' Sections Pre-assembled Channels and Frames at Factory	
<i>Lumber</i>	100 lineal feet of 4' x 8' sheets		None	
	100 lineal feet 2" x 4" support wood			
<i>Other Materials</i>	Nails and Tie-Wire		None	
<i>Form release</i>	1 Gallon		None	
<i>Waterstop</i>	200 lineal feet		None	
<i>Grout for slope</i>	100 lbs of grout		None	
<i>Keyway</i>	200 lineal feet		None	
<i>No. 3 Rebar (2' lengths)</i>	4 per grate section - 200 pcs.		8 per section - 100 pcs.	
<i>Craftsmen Required:</i>	Plumber, Carpenter, Iron Worker, Concrete		Plumber, Carpenter, Iron Worker, Concrete	
<i>Labor:</i>	2 days per 100 feet		1/2 day - 100' run	
	Form Base		N/A	
	Cut and Set Keyway, Waterstop		N/A	
	Pour Base		Set to Grade on Rebar Clips	
	Remove Grates, Set Sidewall Forms		N/A	
	Set Frame and Grates to Sidewall Forms		Monolithic Concrete Pour	
	Re-install Grates			
	Pour Sidewalls		N/A	
	Remove Grates, Remove Forms		N/A	
	Grout in Slope		N/A	
	Re-install Grates		Install Grates	
Total Cost:				



ZURN INDUSTRIES, LLC
 FLO-THRU OPERATION
 1801 PITTSBURGH AVENUE
 ERIE, PA, U.S.A. 16502
 PHONE: 885-ONE-ZURN (855-663-9876)
 FAX: 814-875-1402
 www.zurn.com

Form No. ZMKTG220-36, 7/12