

NOTES:



1. FOR GRAVITY APPLICATIONS ONLY.
2. ALL PROCEPTOR UNITS ARE MANUFACTURED WITH FIBERGLASS REINFORCED PLASTICS. PHYSICAL CHARACTERISTICS AND THICKNESS: POLYESTER RESIN AND E GLASS MINIMUM THICKNESS 1/4" WALL AND 3/8" TOP AND BOTTOM BOWLS.
3. ALL PROCEPTOR UNITS ARE TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS INSTALLATION INSTRUCTION.
4. STANDARD PIPING IS SCH. 40 PVC.
5. GMC/OMC 500 - 3000 UNITS COME STANDARD WITH 4" INLET AND OUTLET (OTHER PIPE SIZE OPTIONS AVAILABLE ON REQUEST).
6. EXTENSION COLLAR TO BE ORDERED TO MEET FINISHED GRADE, CUT ON SITE FOR FINAL ADJUSTMENT AND CAULKED WITH SIKAFLEX BY CONTRACTOR FOR WATERTIGHT SEAL.
7. COVERS AVAILABLE FOR H2O TRAFFIC LOADING, PEDESTRIAN LOADING OR ABOVE GROUND INSTALLATION.
8. CONSULT GREEN TURTLE FOR OTHER SIZES.
9. 30 YEAR WARRANTY AGAINST LEAKS, AND STRUCTURAL FAILURE.
10. U.S. PATENT #5,746,912; CDN PATENT #2,195,822

SPECIFICATIONS


PIPE SIZE: 4 INCH PVC SCH 40
 INSTALLATION: BURIED
 ACCESSWAY SIZE: 24 INCHES

OPTIONS

TOP VIEW



SECTION A-A



TOTAL WET VOLUME: 1500 GAL
 MAX. GREASE CAPACITY: 819 GAL
 MAX SOLIDS CAPACITY: 401 GAL

CONSULT LOCAL AUTHORITIES FOR MINIMUM SIZE OF SEPARATORS

TITLE: PROCEPTOR® F.O.G. SEPARATOR GMC 1500(2)		REV	DATE	DRAWN
PROJECT: WO:		1		
NOTES:		2		
		3	JUNE 03, 2005	L. SIMKINS
		4	JANUARY 4, 2007	L. SIMKINS
		5	NOVEMBER 09, 2009	L. SIMKINS
		6	MARCH 14, 2012	L. SIMKINS
		7	SEPT. 09, 2014	
		8		
		9	APRIL 27, 2017	
		10		
		DRAWN BY: F. CHANDLER		
		DRAWN DATE 9/14/04		



SIZE	DWG. NO.	REV.
A	GMC 1500(2)	9
SCALE:1:40	DO NOT SCALE DRAWING	SHEET 1 OF 1