GMC 500-P TO 2000-P TRIPLE MANWAY (UPC) ABOVE GROUND INSTALLATION

NOTES:

- 1. ENSURE FLOOR IS LEVEL, SMOOTH, AND IS ABLE TO SUPPORT THE WEIGHT OF THE TANKS FULL OF WATER AT INSTALLATION LOCATION.
- MOVE TANKS INTO POSITION. CHECK FIT AND LOCATION OF INLET, OUTLET AND VENT PIPING (WHERE APPLICABLE).
- ENSURE ACCESSWAY IS ACCESSIBLE FOR COVER REMOVAL AND PUMPOUT AS WELL AS ACCESS TO THE INTERIOR. ENSURE ALL OTHER PORTS ARE ACCESSIBLE FOR INSTALLATION AND MAINTENANCE. ALARM PROBES (IF SUPPLIED) SHOULD HAVE SUFFICIENT HEADSPACE FOR REMOVAL TO CALIBRATE OR SERVICE.
- 4. ÉNSURE ARÉA ÁROUND TANK IS HEATED TO PREVENT FREEZING OF WATER IN TANK AND PIPES.
- 5. THE STABILIZATION SUPPORTS MAY BE AFFIXED TO FLOOR IF DESIRED.
- SEISMIC RESTRAINTS TO BE PROVIDED BY OTHERS IF REQUIRED BY LOCAL AUTHORITIES
- INSTALL INLET, OUTLET AND VENT PIPES TO MEET LOCAL PLUMBING CODE.
- 8. PRIOR TO COMMENCING OPERATIONS, FILL TANK WITH CLEAN WATER.
- US PATENT # 5,746,912; CDN PATENT # 2,195,822
- PROCEPTOR SEPARATORS MUST BE INSTALLED IN ACCORDANCE WITH ALL RELEVANT FEDERAL, PROVINCIAL,/STATE, AND LOCAL CODES INCLUDING LOCAL PLUMBING CODE.

